WV.0228 #47

P268 652 368
CERTIFIED MAIL
RETURN RECEIPT REQUESTED

UNION CARBIDE CORPORATION P.O. BOX 180, SISTERSVILLE, WEST VIRGINIA 26175
Silicones and Urethane Intermediates
SILICONES PLANT

April 14, 1987

Ms. Carol Febbo
Air Management Division
U.S. EPA, Region III
841 Chestnut Building
Philadelphia, PA 19107

RE: Notification of Unscheduled Renovations
at Union Carbide's Sistersville, W.V. Facility


Dear Ms. Febbo,

This is to notify you, as required by the provisions of 40 CFR 61.146, that Union Carbide Corporation, Old Ridgebury Road, Danbury, Connecticut 06817, as owner, expects to engage in unscheduled renovation activities through March 1988 which, in the aggregate, are estimated to involve removing 80 linear meters (260 linear feet) or more of friable asbestos on pipes or 15 square meters (160 square feet) or more of friable asbestos used to cover other facility components.

Because the renovation operations are only predicted to occur at Union Carbide's Sistersville facility during the next 12 months, we cannot at this time advise you when each renovation will begin and be completed and exactly how much asbestos will be removed during each renovation. We estimate the total aggregate quantity of asbestos-containing insulation to be removed during unscheduled renovation activities will be approximately 7000 linear feet from piping and 6000 square feet from other equipment.

Removed insulation will be replaced with non-asbestos insulation. All asbestos containing material will be handled in a wetted state in accordance with Section 61.147. The wetted asbestos material will be placed in impermeable sealed plastic bags, delivered to the disposal area (located at the Sistersville Plant), and buried within 24 hours of delivery in accordance with Sections 61.152 and 61.156.

In our opinion, this blanket notification meets the requirements of 40 CFR 61.146 for unscheduled renovation operations. Additional notification will be provided for any single project which, by itself, will involve



UCC 019856

Published by AsbestosClaims.Law
asbestosclaims.law/library/18623/1

removing 80 linear meters or more of friable asbestos from pipes or 15 square meters or more of friable asbestos from other facility components. If you have any questions concerning this notification, please call me at (304) 652-3211, Extension 512.

Sincerely,

A. J. Vandenberg

AJV:slc
1181A
cc: F. E. Dailey
R. L. Foster
J. K. Kyle
E. D. Southard
W. V. Summers
File

UCC 019857